

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 49N N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 32-33

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-31-70

WITNESSES TO CORNER..... 11" Hemlock (¼S NBT) S36°W 10.2'



9" Soft Maple (¼S NBT) N9°E 16.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one Hemlock B.T., bearing S36°E, 40 lks. Found stump, cut 2' high with lower face, notch and scribe marks in excellent condition. Found old scribed post on ground, near corner.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*  
Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 9-21-70