

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 49N N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 21-28

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 5-4-70

WITNESSES TO CORNER..... 12" W. Pine (¼S NBT) S35°W 50.2'



CIRCLE CORNER REGISTERED

14" R. Pine (¼S NBT) S88°W 62.0'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from an original witness; a down jack pine, bearing N70°W 21 lks. Also found remains of a hemlock stump bottom, bearing, S65°E, 29 links. Found wood post on ground, with several trees blazed, near corner.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE 5-4-70
BILLY D. BUCKLER
REGISTERED LAND SURVEYOR