

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49N N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 20-29

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5-14-70

WITNESSES TO CORNER..... 8" Jack Pine (¼S NBT) S75°W 21.6'



7" Jack Pine (¼S NBT) S77°E 17.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one possible witness, a Jack Pine stump bottom, bearing N34°E 21 links.

Have record of a wood post at this corner several years ago. This was apparently destroyed during logging operations.

Found a line tree, east of corner.

Corner lies 30' north of a logging trail.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 9 - 22 - 70
REGISTERED LAND SURVEYOR