

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 49N N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 20-21

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5-14-70

WITNESSES TO CORNER..... 5" B. Spruce (1/4S NBT) N24°E 38.1'



9" Jack Pine (1/4S NBT) S72°E 18.2'

7" Jack Pine (1/4S NBT) S64°W 10.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original Jack Pine witness, bearing N30°E, 24 links.  
Tree down and in poor condition.  
Found remains of bottom notch and both faces, burned but still recognizable.

Found no evidence of use at this corner.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*  
Billy D. Buckler

REGISTERED LAND SURVEYOR

DATE

9-22-70