

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49N N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 28-29-32-33

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8-31-70

WITNESSES TO CORNER..... 17" Red Pine (S33 NBT) S75°E 85.4'



7" W. Pine (S28 NBT) N23°E 42.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from remains of two original witnesses; a Jack Pine stump, bearing S44°W 34 lks; found burned face and notch in evidence. Found stump bottom, bearing N40°E 39 lks. Cor. lies in a wet spruce and jack pine marsh. Distance east to original pine line tree checks (3.95 chs.)

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*  
Billy D. Buckler DATE 9222-70  
REGISTERED LAND SURVEYOR