

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48-49N N.R. 9-10W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 6-1-36-31 Also a township corner.

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 9-10-70

WITNESSES TO CORNER..... 8" W. Pine (S31 NBT) N39°E 12.9'



10" W. Pine (S 6 NBT) S45°E 14.6'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at a $\frac{1}{2}$ " iron bolt, set by unknown surveyor. Distance checks well to an original line tree (664.0') East of here. Record distance is 670.0'. Corner lies in line with a single wire fence to west. Corner lies 30' west of an old cleared north-south roadway.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 9-21-70