

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48-49N N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER ± Cor. bet. Secs. 6-31

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9-10-70

WITNESSES TO CORNER..... 18" W. Pine (±S NBT) N49°E 39.8'



CIRCLE CORNER REGISTERED

18" R. Pine (±S NBT) N68°W 84.3'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one probable B.T., a down W.Pine, 16", bearing N4°E, 25 lks. Found no positive marks on this tree, which has burned and rotted. Position checks well with two original W.Pine line trees, 9.99 chs. east and 26.70 chs. west.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 9-10-70
REGISTERED LAND SURVEYOR