

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 49N N.R. 8-9W

Luce COUNTY


DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 31-36.

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-12-70

WITNESSES TO CORNER..... 14" W. Pine (1/4 S NBT) S24°E 22.1'

14" W. Pine (1/4 S NBT) S62°W 22.8'



AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner replaced at a scribed wood post, set by H. Lawrence, A.L.S.  
Found remains of a tamarack stump, bearing  $138^{\circ}W$  15 links, for a probable bearing tree.

Corner lies  $\frac{1}{2}$  chain South of a small lake and in a spruce marsh.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*  
Billy D. Buckler DATE 8-26-70  
REGISTERED LAND SURVEYOR