

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 9 W

Luce COUNTY

DESCRIPTION OF CORNER Meander corner between Sections 15 and 16 on South shore of small lake.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 7" W. Pine N 73 W 76 1/2 Links (M.C. MPT)

No other available.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced as set by Marcus Schaaf, Reg. Surveyor. Found two old stakes in ground. Found remains of Tamarack B.T. bearing S 60 E, 16 Links. Gov't. notes indicate this tree to be N 60 E, 15 Links. Found wood slab marked (BT) S 31 W, 20 Links at site of old stump bottom (Probable Spruce).

Shown by J. Kitchera and L. Rubick.

Corner was placed and witnessed on 29 May 1958.

SURVEYORS SEAL

SIGNED Billy D. Buckler
BILLY D. BUCKLER
REGISTERED LAND SURVEYOR DATE 6-2-59