

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 9W

Luca

COUNTY

DESCRIPTION OF CORNER Sec. Cor. 1-2-11-12

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 6" R. Pine (S1 NBT) N52°E 69 Lks.

6" R. Pine (S2 NBT) N65°W 37 Lks.

6" W. Pine (S11 NBT) S29°W 71 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced cor. from Y. Pine B.T. stump bearing N29°W 36 Lks. Face and notch in good condition. Cor. is buried in intersection of N-S-E-W firelanes. Cor. placed and wit. 5/20/59 with L. Rubick, Aide.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 8/6/59  
REGISTERED LAND SURVEYOR