

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 9W

Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. 10-11-14-15

DESCRIPTION OF CORNER MONUMENT 2" Iron Pipe buried in Firelanes

WITNESSES TO CORNER 10" J. Pine (S15 NBT) S20° W 25 Lks.

11" J. Pine (S10 NBT) N20° W 51 Lks.

8" J. Pine (S11 NBT) N20° E 49 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced cor. as set by Marcus Schaaf, Reg. Surveyor. Found 2" Iron Pipe in place with J. Pine B.T. N50° E 37 Lks., tree down and in poor condition. Found stp. bottom S30° W 27 Lks. Also found W. Pine N22° W 29 Lks. This appears to be an extra witness tree scribed only with sec. number. Cor. placed and wit. 5/22/59 with L. Rubick, Aide.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 8/6/59
REGISTERED LAND SURVEYOR