

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49-50 NR. 2W.

----- Luce ----- COUNTY

DESCRIPTION OF CORNER ----- Sec. Cor. 1-2-35-36 -----

DESCRIPTION OF CORNER MONUMENT ----- 1" Pipe with 4" Brass Cap -----

WITNESSES TO CORNER ----- 12" R. Oak (S35 NBT) N47° W 55 Lks. -----

----- 13" R. Pine (S1 NBT) S66° E 66 Lks. -----

----- 10" J. Pine (S2 NBT) S26° W 77 Lks. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced cor. from remains of three bearing trees. Y. Pine N64° W  
51 Lks., W. Pine stp. bottom S45° E 51 Lks. and Y. Pine stp.  
bottom S41° W 57 Lks. Cor. buried in intersection of firelines  
to N-S-E-W. Cor. placed and wit. 5/22/59 with L. Rubick, Aide.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED ----- Billy D. Buckler ----- DATE 8/6/59 -----  
REGISTERED LAND SURVEYOR