

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

2 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 49 ^{N.} _{S.} , R. 9 ^{E.} _{W.}	B-9
2. PROPERTY CONTROLLING IN SECTION 35 _____	T. 49 ^{N.} _{S.} , R. 9 ^{E.} _{W.}	1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} _{S.} , R. _____ ^{E.} _{W.}	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-23-72 & 1-25, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-9 South 1/4 Corner of Section 19. O.B.T.'S: Wood Post. Maple 12, S56°E, 37 lks. & Maple 7, N70°W, 90 lks.
- 1 West 1/16 Corner on the North side of Section 35. Not prev. established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-9 Corner placed by single proportionate measurement on a straight line between the S.E. Section Corner of Section 19 and the S.W. Section Corner of Section 19.
- 1 Corner set M.P.O.L. between Section Corner West and 1/4 Corner East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument set at both corners. Bearings:

- B-9 12" W. Pine, N63°W, 4.0'
14" W. Pine, S04°W, 17.0'
- 1 10" J. Pine, N38°E, 10.1'
6" J. Pine, S69°E, 14.2'

SIGNED BY

Billy D. Buckler
Billy D. Buckler

DATE 9-25-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

