

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

LUCE CO.

4 CORNERS

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>49</u> N. S. R. <u>9</u> K. W.	<u>D-5, C-6, F-5, E-7</u>
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11-20 & 11-25, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- D-5 South 1/4 Corner of Section 8. Corner set by Billy D. Buckler L.S. on May 29, 1958. 8" J. Pine, South 121 lks. & 8" J. Pine, N16°E, 76 lks.
- C-6 West 1/4 Corner of Section 17. Corner set by Billy D. Buckler L. S. on June 16, 1958. 7" J. Pine, S23°W, 127 lks. & 8" J. Pine, S85°W, 62½ lks.
- F-5 South 1/4 Corner of Section 9. Corner set by Billy D. Buckler L.S. on May 29, 1958. 10" J. Pine, N53°E 34 lks. & 9" J. Pine, S22°E, 21 lks.
- E-7 S.E. Section Corner of Section 17. Corner set by Billy D. Buckler, L.S. on May 29, 1958. 10" J. Pine, S49°W, 31 lks. & 10" J. Pine, N55°E, 25 lks. & 11" J. Pine, N30°W, 65½ lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-5 Replaced and re-wit corner as set by Buckler in 1958.
- C-6 Re-witnessed Buckler's 1958 corner.
- F-5 Replaced and re-wit corner as set by Buckler in 1958.
- E-7 Replaced and re-wit corner as set by Buckler in 1958.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---------------------------------------|-------------------------------|
| D-5 8" J. Pine Stump, South, 79.6' | F-5 6" J. Pine, S80°W, 133.0' |
| 8" J. Pine, N16°E, 50.16' | 8" J. Pine, N89°W, 136.9' |
| 8" J. Pine, N73°W, 72.6' | 8" J. Pine, N08°W, 37.1' |
| 6" J. Pine, S65°W, 10.5' | 4" J. Pine, N38°E, 85.0' |
| 8" J. Pine, N63°E, 34.5' | DNR Mont. inside of 2" pipe. |
| DNR Mont. inside of 2" Pipe | |
| C-6 8" J. Pine, S60°E, 53.1' | E-7 10" J. Pine, N55°E, 16.5' |
| 6" J. Pine, N30°W, 84.0' | 6" J. Pine, N45°W, 58.6' |
| 6" J. Pine, N10°W, 93.6' | 8" J. Pine, N70°W, 64.4' |
| 8" J. Pine, N45°E, 96.7' | 6" J. Pine, N36°E, 28.8' |
| Mont. 2" Iron Buried in N-S Firelane. | DNR Mont. |

SIGNED BY

Gerald L. Wiggins

DATE

9-10-86

Gerald L. Wiggins
SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

