

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

LUCE CO.

3 CORNERS

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> ^{N.} S. , R. <u>9</u> ^{E.} W.	<u>D-7, F-7, K-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, S., R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, S., R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11-25 & 11-27, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- D-7 South 1/4 Corner of Section 17. Corner set by Billy D. Buckler on May 29, 1958. 9" J. Pine, N33°E, 12.87' & 9" J. Pine, South, 16.17'.
- F-7 South 1/4 Corner of Section 16. Corner set by Billy D. Buckler on May 29, 1958. 8" J. Pine, N20°E, 48 lks. & 9" J. Pine, S40°W 40 lks.
- K-5 S.E. Sec. Cor. of Section 11. Corner set by Dean DeLaMater on October 1952. 10" R. Pine, S50°E, 22 lks. & 20" R. Pine, N19°W, 45 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-7 Replaced and re-witnessed Buckler's 1958 corner.
- F-7 Re-witnessed Buckler's 1958 corner.
- K-5 Re-witnessed DeLaMater's 1952 corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-7 Buried DNR Monument at corner. 9" J. Pine Stump, N33°E, 12.87' & 8" W. Birch, N47°W, 44.0' 5" R. Pine, N10°W, 56.5' & 10" W. Birch, N70°E, 69.0'.
- F-7 Buried 2" Iron. 10" J. Pine, N69°E, 35.65' & 10" J. Pine, N13°E, 58.1' & 8" J. Pine, N74°W, 65.1' & 6" J. Pine, S68°E, 19.5'
- K-5 DNR Monument. 26" W. Pine, N57°W, 61.1' & 8" W. Pine, N45°E, 23.7' & 10" R. Pine, S70°E, 28.0' & 12" W. Pine, S20°W, 20.2'.

SIGNED BY _____

Gerald L. Wiggins

Gerald L. Wiggins

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

DATE 9-10-86



FOR STATE AND UNITED STATES AGENCIES: