

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LUCE	County	1 Corner Located In:	Corner Code
1. Public Land Survey		T 49N R 9W	M-6
		T _____ R _____	
		T _____ R _____	
		T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4 Lot No \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	19	20	21	22	23	24	25	26	27	28	29	30	31
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Gerald L. Wiggins, in a field survey on 5-23, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6 East 1/4 Corner of Section 13. Placed by Billy D. Buckler R.L.S. on 5-4-76. Bearings:  
 16" R. Pine, N86°E, 21.0' & 15" R. Pine, N60°W, 50.4' & 15" R. Pine, S47°W, 79.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

M-6 Buckler's three Red Pine witness trees still in place and green however 2" Iron Pipe set in concrete was missing. Replaced from Buckler's witness trees a DNR Monument and marked one additional witness tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 DNR Monument buried in East edge of road.

Buckler's three witness trees still present and green. Marked a 14" R. Pine, S45°E, 35.35'.

Signed by

*Gerald L. Wiggins*

Date

9-13-90

Surveyor's Michigan License No. 23521

