

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-----------|
| 1. Public Land Survey | T <u>49N</u> R <u>9W</u> | <u>L7</u> |
| | T <u>49N</u> R <u>9W</u> | <u>L5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on May 06, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L7) Quarter corner common to Sections 13-24. Corner previously recorded by Billy D. Buckler in 1956 as a 1" pipe with a 4" brass cap from the remains of a possible original bearing tree, old squared birch, and wood stake. 1956 NBTs are: 15" Hemlock N39W 83.5 links, 15" Hemlock S86W 38.5 links. Monument re-witnessed in 1961 by Buckler with the following: 12" S. Maple N27W 58 links, 10" S. Maple S74 E 70 links. Found no subsequent record.

(L5) Quarter corner common to Sections 12-13. Corner previously recorded by Billy D. Buckler RLS, in 1976 as a 5/8" iron buried in firelane with the following NBTs: 22" Red Pine S20W 35.8', 15" Red Pine S77E 50.6'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L7) Found and accepted a 1" pipe with 4" brass cap at record bearing and distance from the 1961 NBTs, both in good condition, and at record bearing and distance from the remains of the 1956 NBTs, the Hemlock SW being a stump, and the Hemlock NW being dead. Marked two new witness trees as described below.

(L5) Found and accepted 5/8" iron bar buried at the corner at record bearing and distance from both 1976 NBTs, which are in good condition. Placed measuring nails with tags in the 1976 witnesses and took two new NBTs as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L7) Found 1" pipe with 4" brass cap Blazed, scribed, and set measuring nails in the following new bearing trees: 10" Y. Birch N35E 4.05' "1/4S NBT" 10" Hemlock S10E 18.5' "1/4S NBT" Set measuring nails in the 1961 NBTs: 18" S. Maple N27W 38.65' 16" S. Maple S74E 46.85' placed a 5" hemlock post adjacent to the monument.	(L5) Found 5/8" iron bar Blazed, scribed, and set measuring nails in the following new bearing trees: 3" White Pine S05E 22.8' "1/4S NBT" 10" Red Pine S70E 49.9' "1/4S NBT" Set nails/tags in 1976 NBTs: 24" R. Pine S20W 36.65' 18" R. Pine S77E 51.0'
---	---



Signed by Stephan J. Szyszkoski Date 8-4-93
 Surveyor's Michigan License No. 33986