

#105

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce (County)	Located In:	Corner Code #/
1. Public Land Survey	T 49N R 9W	C3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 4 T 49N R 9W	J
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	4	5	6	7	8	9	10	11	12	13	14	15	16
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5	10	11	12	13	14	15	16	17	18	19	20	21	22
6	13	14	15	16	17	18	19	20	21	22	23	24	25
7	16	17	18	19	20	21	22	23	24	25	26	27	28
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9	22	23	24	25	26	27	28	29	30	31	32	33	34
10	25	26	27	28	29	30	31	32	33	34	35	36	37
11	28	29	30	31	32	33	34	35	36	37	38	39	40
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13	34	35	36	37	38	39	40	41	42	43	44	45	46

I, Stephan J. Szyszkoski, in a field survey on June 22, 1992, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C3) Section corner common to sections 5-6-7-8. Corner previously recorded by Billy D. Buckler as re-monumented in 1959 at a position determined by Marcus Schaaf, ca. 1920's, from original evidence. The corner was monumented with a 2" pipe and the following NBT's: 8" J. Pine, N70W 54.5 Links (S6 NBT), 7" J. Pine N34E 36.5 Links (S5 NBT).

(1-Sec. 4) West 1/16 corner between Sec. 4, T49N-R9W and Sec. 33, T50N-R9W. Corner previously recorded by Billy D. Buckler in 1971. Buckler's witnesses: 8" J. Pine North, 31.6'; 8" R. Pine S03W 106.0'. Buckler placed a 1" pipe with 4" aluminum cap at the corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C3) Found 2"x24" iron pipe cast in a 7"x7" square concrete base at the surface of the intersection of firelines N-S-E-W, at record bearing and distance from Buckler's NBTs. Lowered the monument so that the top of the pipe is 6" below the road surface. Scribed new top blaze "S5" on J. Pine NE NBT, and placed measuring nails in both 1959 NBTs. Marked two new bearing trees, described below.

(1-Sec. 4) Found Buckler's monument and accessories as noted above. Buckler's R. Pine blazed overgrown. Scribing visible on the J. Pine. Corner is 8' north of the centerline of E-W fireline. Scribed top blaze "1/16" and placed measuring nails in Buckler's NBT's and marked two new witness trees, as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C3) 2"x24" iron pipe.
Blazed, scribed, and set measuring nails in the following new bearing trees:
12" J. Pine S53E 63.37' "S8 NBT"
10" J. Pine S30W 49.65' "S7 NBT"
Re-measured to the 1959 NBTs:
12" J. Pine N36E 25.56'
10" J. Pine N67W 35.75'
7" squared post adjacent to corner on the east.



(1-Sec. 4) Found 1" pipe with 4" Aluminum cap. Blazed, scribed, and placed measuring nails in the following new bearing trees:
12" J. Pine N43W 8.25' mrd "1/16 NBT"
13" J. Pine S34E 53.44' mrd "1/16 NBT"
Set measuring nails in the record NBTs:
11" J. Pine N03E 31.84' mrd "1/16"
12" R. Pine S07W 106.35' mrd "1/16"
Placed 5" squared R. Pine post adjacent to and south of the monument.

Signed by Stephan J. Szyszkoski Date 10-15-92
Surveyor's Michigan License No. 33986