

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Luce

(County)

Located In:

Corner Code F1

- |                                       |                          |           |
|---------------------------------------|--------------------------|-----------|
| 1. Public Land Survey                 | T <u>49N</u> R <u>9W</u> | <u>F1</u> |
|                                       | T _____ R _____          | _____     |
|                                       | T _____ R _____          | _____     |
|                                       | T _____ R _____          | _____     |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____     |
|                                       | S _____ T _____ R _____  | _____     |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____     |
|                                       | S _____ T _____ R _____  | _____     |

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jun 25 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F1) Quarter corner common to Section 4 T49N-R9W and Section 33 T50N-R9W. Perpetuated and recorded by the undersigned in 1992: 1" pipe with 4" aluminum cap. 10" J. Pine S70E 68.65', 10" J. Pine S34W 53.1', 9" J. Pine N48E 19.95', 10" J. Pine S29E 48.78', 2" iron pipe N88W 3.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F1) Recovered the corner as described, and at record bearing and distance from three of the five 1992 witnesses. The Jack pines S34W and N48E have been destroyed. Left the monument in place and made two new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F1) Found 1" pipe with 4" aluminum cap. Made two additional witnesses:  
 10" Rd Sign S14W 15.5'  
 Blazed, scribed, and set measuring nail with tag in:  
 10" R. Pine S50E 58.65' "1/4S NBT"  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 7/25/01  
 Surveyor's Michigan License No. 33986