

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Luce</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>49N</u> R <u>9W</u>	<u>A11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>30</u> T <u>49N</u> R <u>9W</u>	<u>9</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A11 Dec 04 2001
 9 Nov 25 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(A11) Corner common to Sections 30-31 T49N-R09W and 25-36 T49N-R10W. 1972: Reestablished by Billy D. Buckler RLS: Corner reestablished by proportionate measurement and on a straight line bet. two Sec. Cors. No evidence of original corner. Placed 1" pipe with 4" aluminum cap at corner. New Bearings: 14" W.Pine S43E 57.7', 14" twin W.Pine N75E 38.0'.
 (9-Sec. 30) East 1/16 corner, Section 30. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A11) Recovered the 1972 monument in good condition and at record bearing and distance from the W.Pine NBTs, both in good condition with overgrown blazes. Did not make measurements to Section Corners north or south during my survey. Left the monument in place and made new witnesses as described below.
 (9-Sec. 30) Established the corner midway and on a straight line between Center of Section and 1/4 corner 1323.58' west and east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A11) Found 1" ID I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:	(9) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
* 20" W.Pine N70E 38.4' "S30"	6" J. Pine N26E 17.9' "E1/16 8T"
* 20" W.Pine S40E 57.8' "S31"	6" J. Pine N46W 7.95' do
10" J. Pine N79W 4.55' "S25 NBT"	6" J. Pine S65W 20.7' do
8" W.Pine N22W 10.25' do	5" R. Pine S48E 22.3' do
Set Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1972 NBT.	Placed a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/02