

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce	Located in:	Corner Code #	
(County)			
1. Public Land Survey	T 49N R 9W	C9	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Dec 04 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9			●										
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:


(C9) Corner common to Sections 19-20-29-30. 1850: Established by Harvey Mellen, D.S.: Set post at corner of Sections 19,20,29,30. Spruce 12 S85E 32, Spruce 5 N47W 14. 1952: Original position remonumented by D.C.DeLaMater RLS: This corner was pointed out to me by B.McTiver, District Forester, of Newberry. Remains of one original B.T. still in place, poor condition. Set 1" Pipe with 4" Brass cap. 8" Spruce N45E 0.5 links, 8" W.Pine N24W 54 links. MDNR records in Newberry office show additional NBT R.Pine N35E 31 links, undated, but probably by Mr. DeLaMater or Billy D. Buckler, RLS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C9) Recovered the 1952 monument in good condition and at record bearing and distance from the W.Pine and R.Pine NBTs, both in good condition with overgrown blazes. The Spruce NBT is dead and gone. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C9) Found 1"ID Iron pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in:
 * 12" R.Pine N32E 20.25' "S20"
 * 16" W.Pine N26W 35.5' "S19"
 8" W.Pine S20E 11.1' "S29 NBT"
 5" Spruce S22W 9.2' "S30 NBT"
 2" PVC pipe, projecting 6' adjacent.
 Bearings are magnetic. Distances are to nail with tag. * denotes previous NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/02