

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>49N</u> R <u>9W</u>	C11	
	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Dec 04 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (C11) Corner common to Sections 29-30-31-32. 1850: Established by Harvey Mellen: N13'E between 31&32...79.91 Set post at corner 29-30-31-32. Maple 8 S34E 47, Beech 12 N62W 37. 1956: Reestablished by Billy D. Buckler RLS: Set Section Corner on N. and S. line of blazes. Old blaze on Hemlock facing the location (50 years old). Distance checks with 1/4 corner 1/2 mile north. 1" pipe with 4" brass cap. 16" Hemlock N65W 28.5 links, 9" H. Maple S50E 30 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (C11) Original post and accessories were not recovered. Found the 1956 monument in good condition and at record bearing and distance from the remaining NBT Hemlock NW, in good condition. The H.Maple NBT is gone. The Hemlock with old blaze noted in the record is still present. Distances N,S,E,W to adjacent 1/4 corners are 40.247 (39.955 R), 39.838 (39.955 R), 40.124 (40.22 R), 39.907 (40.08 R), respectively. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (C11) Found 1" ID I.Pipe with 4" brass MI Dept. of Conservation tablet. Blazed, scribed, and set measuring nails in:
 * 24" Hemlock N60W 19.65 "S30"
 6" Balsam S78E 11.65' "S32 NBT"
 8" Maple N44E 19.75' "S29 NBT"
 5" Balsam S34W 22.0' "S31 NBT"
 Bearings are magnetic. Distances are to nail with tag. * denotes 1956 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/02