

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>49N</u> R <u>9W</u>	<u>G11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 06 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 Corner common to Sections 27-28-33-34. 1850 - Established by Harvey Mellen, Deputy Surveyor: "Set post corner of Sections 27,28,33, & 34. Y.Pine 18 S6W 54 links, Sp. Pine 10 N41E 13 links". 1970 - Remonumented by Billy D. Buckler, RLS, and recorded in Liber 1 of LCRC, Page 50, Luce County Records. Mr. Buckler remonumented the corner at record bearing and distance from the two original BTs, the Spruce Pine (Jack Pine) down with both faces and all scribe marks in excellent condition, and the Yellow Pine (Red Pine) green and standing, with scribe marks plain and in excellent condition. Mr. Buckler placed a 1"ID iron pipe with a 4" dia. aluminum State of Michigan tablet at the corner position and made the following new bearing tree: 10" Red Pine N46W 50.2' marked "S28 NBT".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The 1970 monument was found removed from its proper position, having been extracted from the ground and placed against a nearby tree by persons unknown. Remonumented the 1970 position of record, at record bearing and distance from the 1970 Red Pine NBT, now 14" DBH and in good condition with markings visible, and at record bearing and distance from the original BT Yellow Pine, now 24" DBH, in excellent condition with upper blaze open and scribing visible. The Spruce Pine OBT noted in the 1970 record was not recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 1"IDx36" I.pipe with plastic cap "MICH DNR PS33986" at the 1970 position of record. Set measuring nails in:

- 24" Red Pine S09W 35.95' *
- 14" Red Pine N40W 50.8' **
- 5" Red Pine N20W 17.5' mrkd "S28 NBT"
- 8" W. Pine S87W 11.0' mrkd "S33 NBT"

Bearings are magnetic. Distances are to nail with plastic tag set in the side of the bearing tree. * denotes the original

BT, ** denotes 1970 NBT.



Stephan J. Szyszkoski

Signed by _____
 Surveyor's Michigan License No. 33986

Date 12/7/04