

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R 09W	I 4
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on Sept. 11, 2006 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I4) Quarter corner common to Sections 10 and 11. 1850 - Established by Harvey Mellen, Deputy Surveyor: Set post midway and on the Section line between Section corners 40.06 chains north and south. Spruce Pine 16 N11W 15 links, Spruce Pine 12 S42E 12 links. 1959 - Original position perpetuated by Billy D. Buckler RLS: Replaced corner as set by Marcus Schaaf, Reg. Surveyor. Found 2" Iron pipe [buried in N-S firelane] in place witnessed by pits and mounds. Found remains of one J.Pine B.T. N11W 15 links in poor condition. Mr. Buckler marked the following new bearing trees: 8" J.Pine S38E 36.5 links, 9" J.Pine N88E 45 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I4) Recovered the 2" Iron pipe of record, in good condition, buried in the center of a N-S firelane. None of the record BTs or NBTs were recovered. Accepted same as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I4) Found 2" ID I.pipe, buried. Set a 5/8"x18" rebar with plastic cap stamped "MICH DNR LS33986" in said pipe. Set measuring nail with MDNR tag in the side of the following trees:
 12" R.Pine N70W 247.33' mrkd "1/4S NBT"
 10" R.Pine N54E 68.86' do
 6" R.Pine S02W 148.52' do
 9" R.Pine S09W 179.35' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/25/07

Surveyor's Michigan License No. 33986