

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R 09W	I 5
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File  
Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5									●				
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Sept. 7, 2006 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 (I5) Corner common to Sections 10-11-14-15. 1850 - Established by Harvey Mellen, Deputy Surveyor: Set post. Spruce Pine 8 N50E 37 links, Spruce Pine 12 S30W 27 links. 1959 - Perpetuated by Billy D. Buckler, RLS: Replaced corner as set by Marcus Schaaf, Reg. Surveyor. Found 2" Iron pipe [buried in firelane] in place with J.Pine N50E 37 links, tree down and in poor condition. Found stump bottom S30W 27 links. Also found W.Pine N22W 29 links. This appears to be an extra witness tree scribed only with Sec. Number. Mr. Buckler made the following new bearing trees: 10" J.Pine S20W 25 links, 11" J.Pine N20W 51 links, 8" J.Pine N70E 49 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (I5) Recovered the 2" Iron pipe of record, in good condition, buried, and at record bearing and distance from the 1959 witnesses, now all dead. The J.Pine NBTs N20W and N70E have been cut at 4' high. The J.Pine S20W is a stump. Accepted the 2" I.pipe as a careful and faithful perpetuation of the position of the original corner. The original BTs were not recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (I5) Found 2" ID I.pipe, buried. Set a 5/8"x18" rebar with plastic cap stamped "MICH DNR LS33986" in said pipe. Set measuring nail with MDNR tag in the side of the following trees:  
 10" W.Pine S56W 17.4' mrkd "S15 NBT"  
 6" W.Pine S02W 11.0' do  
 11" J.Pine S23E 33.75' "S14 NBT"  
 8" J.Pine S64E 30.72' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/25/07

Surveyor's Michigan License No. 33986