

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R 09W	J 3
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on Sept. 27, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3										●			
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 (J3) Quarter corner common to Sections 2 and 11. 1850 - Established by Harvey Mellen, Deputy Surveyor, midway and on line between Section corners 40.10 chains east and west. Set post. Spruce Pine 12 N14E 9 links, Spruce Pine 10 S1W 43 links. 1976 - Reestablished midway and on line between Section corners by Billy D. Buckler, RLS. Set 1" pipe with 4" aluminum cap. 8" W.Pine N38E 29.8', 8" J.Pine N47W 19.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (J3) Recovered the 1976 monument, a 1" ID I.pipe with a 4" dia. aluminum MDNR cap, in good condition and at record bearing and distance from the remaining NBT W.Pine NE, in good condition. The J.Pine NBT NW was not recovered. My measurements show that this monument is located S07W, 5.6' from the midpoint position intended in 1976 and I accept same as a careful and faithful reestablishment of the position of the original corner. The corner lies on the N. side of an E-W trail and the W. side of a trail South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (J3) Found 1" ID I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 16" W.Pine N41E 30.3' mrkd "1/4S" 1976 NBT  
 12" J.Pine N56W 33.5' mrkd "1/4S NBT"  
 10" J.Pine S09W 23.5' do  
 5" J.Pine S57E 27.82' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/25/07

Surveyor's Michigan License No. 33986