

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R 09W	J 5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on Sept. 26, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (J5) Quarter corner common to Sections 11 and 14. 1850 - Established by Harvey Mellen, Deputy Surveyor: Set post midway and on the Section line between Section corners 40.23 chains east and west. Y.Pine 14 N55E 38 links, Spruce Pine 14 S9E 46 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (J5) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record, midway and on the Section line between Section corners 2656.35' east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (J5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 5" J.Pine S12E 12.65' mrkd "1/4S NBT"
 8" J.Pine S78W 23.92' do
 6" J.Pine N01W 35.55' do
 5" J.Pine N47E 32.67' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/25/07

Surveyor's Michigan License No. 33986