

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>09W</u>	<u>K 3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. <u> </u> , Recorded Plat <u> </u>		
5. Private Claims		

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Sept. 26, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K3) Corner common to Sections 1-2-11-12. 1850 - Established by Harvey Mellen, Deputy Surveyor: Set post. Y. Pine 22 N29W 36 links, Spruce Pine 10 S29E 10 links. 1959 - Corner remonumented by Billy D. Buckler RLS "from Y.Pine B.T. stump bearing N29W 36 links. Face and notch in good condition. Corner is buried in intersection of N-S-E-W firelanes. Set 1" pipe with 4" brass cap. New bearing trees: 6" R.Pine N52E 69 links, 6" R.Pine N65W 37 links, 6" W.Pine S29W 71 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K3) The original post and accessories were not recovered. Found the 1959 monument of record, in good condition and at record bearing and distance from the 1959 NBTs. NBTs NE and SW are in good condition. The NBT NW is a cut stump. Also found a buried 2" ID iron pipe 1.2' west of the monument of record. This 2" pipe is not of record but was very likely set by Marcus Schaaf, RLS, possibly in the 1920's or 1930's. Mr. Schaaf remonumented a number of corners in this area and his work was well known to Mr. Buckler. It is likely that Mr. Buckler did not find Mr. Schaaf's monument and was not aware of its existence. It is further likely that Mr. Buckler would have accepted same had he found it, as he did monuments placed by Mr. Schaaf at other corners on Section 11. Upon this basis I accept the 2" iron pipe as a careful and faithful perpetuation of the position of the original corner. I removed the 1959 monument of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K3) Found 2" ID I.pipe buried in firelane intersection. Drove 5/8"x18" rebar with plastic cap stamped "MICH DNR LS33986" in its center. Set measuring nail with MDNR tag in the side of:
 7" J.Pine N23W 42.85' mrkd "S2 NBT"
 14" R.Pine S20E 31.1' "S12 NBT"
 14" R.Pine N56E 40.9' mrkd "S1" (1959 NBT)
 15" W.Pine S30W 46.6' mrkd "S11" do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/25/07

Surveyor's Michigan License No. 33986