

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	S <u>11</u> T <u>49N</u> R <u>09W</u>	<u>16</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on Sept 26, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (16-Sec. 11) East 1/16 corner, Sec. 11. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (16-Sec. 11) Established the corner midway and on the Section line between Quarter corner 1328.18' west and Section corner 1328.18' east. The position for the corner falls on the root of a Spruce tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (16) Set 5/8"x18" rebar with plastic cap stamped "MICH DNR LS33986", driven in root of Spruce tree.
 Set measuring nail with MDNR tag in the side of:
 6" Spruce N78W 5.27' mrkd "E1/16 BT"
 11" J.Pine N19E 29.0' do
 6" Spruce S35E 34.6' do
 14" J.Pine N18W 36.15' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/25/07

Surveyor's Michigan License No. 33986