

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 26 T 49N R 9W	9
	S 26 T 49N R 9W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

02/28/2008
 02/28/2008

I, Stephan J. Szyszkoski, in a field survey on _____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(9-Sec. 26) East 1/16 corner, Section 26. Not established in the original survey.

(5-Sec. 26) North 1/16 corner, Section 26. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 26) Established the corner midway and on a straight line between Center of Section 1320.61' west and Quarter corner 1320.61' east.

(5-Sec. 26) Established the corner midway and on a straight line between Center of Section 1336.15' south and Quarter corner 1336.15' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" W.Birch S56W 17.85' mrkd "E1/16 BT"
 13" Hemlock South 33.2' do
 11" Hemlock N14E 34.05' do
 17" Maple East 5.35' do
 Bearings are magnetic.

(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" W.Pine N85E 28.5' mrkd "N1/16 BT"
 15" R.Pine N06E 13.43' do
 15" W.Pine S19W 51.4' do
 13" R.Pine N44W 23.08' do
 Bearings are magnetic.

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/18/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities