

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T 49N R 9W T _____ R _____	K10
2. Property Controlling in Section	S 26 T 49N R 9W S _____ T _____ R _____ S _____ T _____ R _____	2
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

02/14/2008

02/14/2008

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(2-Sec. 28) East 1/16 corner between Sections 23 and 26. 1976 - Established by Billy D. Buckler RLS midway and on line between Section and Quarter corners. The 1976 record was erroneously filed as describing 1/16 corner #16 of Sec. 26. Set 1" pipe with 4" aluminum cap. 6" Hemlock N25W 10.5', 8" W.Birch N57E 4.0'.

(K10) Quarter corner common to Sections 25-26. 1976 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. 20" W.Pine N21E 63.2', 16" W.Pine S84W 17.0', 6" W.Birch S32E 19.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 26) The 1976 monument was not recovered. Remonumented the corner in the 1976 position, at record bearing and distance from the 1976 BTs, both recovered in good condition. I observe that the position is less than 1 foot from the midway position intended in 1976 and I accept same as a careful and faithful establishment of the position of the corner.

(K10) The 1976 monument was not recovered. Reestablished the 1976 position at record bearing and distance from the remaining 1976 NBTs W.Pine NE and W.Pine SW, both in good condition. This position was found to be 1.6' from the proportionate position intended in 1976 and I accepted same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 10" W.Birch N58E 4.23' mrkd "E1/16" 1976 BT  
 10" Hemlock N24W 10.7' do do  
 7" Hemlock S69W 14.3' mrkd "E1/16 BT"  
 9" W.Pine S04E 18.65' do  
 Bearings are magnetic.

(K10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 20" W.Pine S86W 17.8' mrkd "1/4S" 1976 NBT  
 26" W.Pine N27E 63.7' do do  
 7" W.Pine S08E 19.55' mrkd "1/4S NBT"  
 9" W.Pine N89E 20.45' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 03/18/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities