

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 9W	K11
	T 49N R 9W	I9
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on K11 02/14/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K11) Corner common to Sections 25-26-35-36. 1976 - Reestablished by double proportionate measurement to the original record by Billy D. Buckler RLS. Set 1" pipe with MDNR cap. 8" W.Pine S62W 46.0', 12" W.Pine S79E 67.0'.

(I9) Corner common to Sections 22-23-26-27. 1956 - Remonumented in the original position by Billy D. Buckler RLS from one W.Pine B.T. rotted, notch remaining on stump. Found a squared post at the corner position. Set 1" pipe with 4" brass cap. 6" W.Pine N60E 115 links, 5" W.Pine N68W 58 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K11) Found the 1976 monument in good condition and at record bearing and distance from the 1976 NBTs, both in good condition. This corner is being recorded to update the accessories.

(I9) Found the 1956 monument in good condition and at record bearing and distance from the 1956 NBTs, both in good condition. Snow cover prevented discovery of any evidence of the original bearing trees. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K11) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 16" W.Pine S74E 67.75' open blazes 1976 NBT  
 12" W.Pine S67W 46.15' do do  
 6" Tamarack S64E 27.3' mrkd "S36 NBT"  
 6" B.Spruce N10E 34.25' "S25 NBT"  
 Bearings are magnetic.

(I9) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 13" W.Pine N61E 76.28' mrkd "S23" 1956 NBT  
 13" W.Pine N64W 39.0' "S22" do  
 11" W.Pine S83E 70.3' "S26 NBT"  
 13" W.Pine S36W 45.4' "S27 NBT"  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

