

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 9W	K9
	T 49N R 9W	I11
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on K9 02/06/2008 and I11 12/12/2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K9) Corner common to Sections 23-24-25-26. 1956 - Remonumented in the original position by Billy D. Buckler RLS from one W.Pine B.T. (down) in good condition. Set 1" pipe with 4" brass cap. 10" W.Pine N20W 80 links, 8" W.Pine S173E [sic] 70.5 links, 7" W.Pine S29E 49 links.

(I11) Corner common to Sections 26-27-34-35. 1970 - Remonumented by Billy D. Buckler RLS "as set by H. Lawrence, RLS. Found post in place, new witnesses and remains of two original Pine witnesses, bearing S57E 44 links, and N63W 68 links". Set 1" pipe with 4" aluminum cap. 11" R.Pine S72E 5.0'. Witnesses by H.Lawrence: 18" Pine stub S10E 23.3', 14" J.Pine S70W 31.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K9) Found the 1956 monument in good condition and at record bearing and distance from the remaining 1956 NBTs. Both W.Pine NBTs SE are in good condition. Snow cover prevented the discovery of any evidence of the original B.T.s. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(I11) Found the 1970 monument in good condition and at record bearing and distance from the NBTs noted in the 1970 record. The R.Pine SE is dead, the J.Pine SW is now a stump, the Pine stub SE is still in place. Snow cover prevented discovery of any remaining evidence of the original BTs. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K9) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 21" W.Pine S70E 46.97' mrkd "S25" 1956 NBT
 22" W.Pine S30E 32.48' do do
 15" W.Pine N31E 10.04' "S24 NBT"
 9" W.Pine S64W 25.1' "S26 NBT"
 Bearings are magnetic.

(I11) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 14" W.Pine N02E 37.0' mrkd "S26 NBT"
 7" W.Pine S60E 19.0' "S35 NBT"
 12" R.Pine S41W 20.4' "S34 NBT"
 10" W.Pine N41W 46.6' "S27 NBT"
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/18/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities