

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____ T 49N R 9W T _____ R _____	J11
2. Property Controlling in Section	S 35 T 49N R 9W S _____ T _____ R _____ S _____ T _____ R _____	1
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	I 02/25/2008 J11 02/26/2008	

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11										●			
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on J11 02/26/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(1-Sec. 35) West 1/16 corner between Sections 35 and 26. 1984 - Established by Billy D. Buckler RLS midway and on line between Section corner West and 1/4 corner East. Set 1" ID I.pipe with 4" alum. MDNR cap. 10" J.Pine N38E 10.1', 6" J.Pine S69E 14.2'.

(J11) Quarter corner common to Sections 26 and 35. 1976 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. No evidence of the original corner. Set 1" ID I.pipe with 4" alum. MDNR cap. 8" J.Pine N88W 12.5', 8" J.Pine N46E 6.6', 6" R.Pine S40E 35.3'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(1-Sec. 35) Found the 1984 monument, in good condition, at the record position, and at record bearing and distance from the 1984 witnesses. The J.Pine NE is standing dead, the J.Pine SE (the tree is, in fact, a W.Pine) in good condition. Accepted the monument as a careful and faithful establishment of the position of the corner.

(J11) Found the 1976 monument in good condition, at the record position, and at record bearing and distance from the remaining 1976 NBT R.Pine SE, in good condition. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(1) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" W.Pine S64E 14.75' mrkd "W1/16" 1984 BT  
 9" W.Pine S69W 13.3' mrkd "W1/16 BT"  
 7" W.Pine N53W 24.2' do  
 18" W.Pine N68E 14.15' do  
 Bearings are magnetic.

(J11) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" R.Pine S37E 36.05' mrkd "1/4S" 1976 NBT  
 8" R.Pine S72E 10.3' mrkd "1/4S NBT"  
 6" W.Pine N11E 8.55' do  
 9" W.Pine S83W 27.65' do  
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*  
 Surveyor's Michigan License No. 33986

Date 03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

