

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T 49N R 9W	G5
	T 49N R 9W	H5
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on G5 05/23/2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G5) Corner common to Sections 9-10-15-16. 1952 - Remonumented by Dean C. DeLaMater RLS: "Corner had been previously located and perpetated by Marcus Schaaf, Registered Land Surveyor". Set 1" pipe with 4" brass cap. 24" Red Pine N4W 47 links, 24" Red Pine N53E 30 links.

(H5) Quarter corner common to Sections 10-15. 1959 - Corner remonumented by Billy D. Buckler RLS: "Replaced cor. as set by Marcus Schaaf, Reg. Surveyor. Found Iron pipe witnessed by pits and mounds." 2" Iron pipe buried in E-W firelane. 8" J.Pine S64E 54 links, 7" R.Oak N20E 32.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G5) Found the 1952 monument in good condition and at record bearing and distance from the 1952 witnesses, both in good condition. Made new witnesses as described below. This corner is being recorded to update the accessories.

(H5) Found the 2" iron pipe of record in good condition and at record bearing and distance from the remaining NBT R.Oak NE, in good condition. This corner is being recorded to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G5) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 26" R.Pine North 32.08' mrkd "S9" 1952 NBT
 24" R.Pine N51E 21.05' "S10" do
 9" W.Pine S36W 20.63' mrkd "S16 NBT"
 13" J.Pine S63E 27.92' "S15 NBT"
 Bearings are magnetic.

(H5) Found 2" Iron pipe in E-W firelane. Set measuring nail with MDNR tag in the side of:
 11" R.Oak N24E 21.45' mrkd "1/4S" 1959 NBT
 10" J.Pine N60E 35.5' mrkd "1/4S NBT"
 4" J.Pine S01E 45.65' do
 13" J.Pine S12E 32.55' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

