

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 9W	H3
	T 49N R 9W	I2
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4					3	2	1			
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on H3 09/11/2006 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H3) Quarter corner common to Sections 3 and 10. 1971 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1" pipe with 4" aluminum cap. 8" J.Pine S09W 18.3', 10" J.Pine N26.5W 32.1'. Corner lies in south wheel rut of E-W firelane.

(I2) Quarter corner common to Sections 2 and 3. 1972 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1" pipe with 4" aluminum cap. 9" J.Pine N89E 32.2', 9" J.Pine N44E 35.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H3) Found the 1971 monument in good condition and at record bearing and distance from the remaining 1971 NBT J.Pine SW, in good condition. This corner is being recorded to update the accessories.

(I2) Found the 1972 monument in good condition, and at record bearing and distance from the remaining NBT J.Pine N89E (measured here as S85E), in good condition. This corner is being recorded to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H3) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 10" J.Pine S09W 18.4' mrkd "1/4S" 1971 NBT
 7" J.Pine S46E 21.85' mrkd "1/4S NBT"
 7" J.Pine N41E 15.6' do
 9" J.Pine N34W 22.3' do
 Bearings are magnetic.

(I2) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" J.Pine S85E 32.6' mrkd "1/4S" 1972 NBT
 6" J.Pine N67E 3.32' mrkd "1/4S NBT"
 6" J.Pine S73W 4.15' do
 7" J.Pine N21W 21.92' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

