

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 9W	G3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 15 T 49N R 9W	2
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3							●						
4	7		8		9		10		11		12		
5									●				
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on G3 09/11/2006 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(G3) Corner common to Sections 3-4-9-10. 1958 - Corner recovered by Billy D. Buckler RLS: Found 2" iron pipe with [BT] stump bottom bearing S39E 126 links. Corner is in intersection of N-S-E-W firelanes. 6" Jack Pine N52W 43 links, 8" Jack Pine S33W 71 links.

(2-Sec. 15) East 1/16 corner between Sections 10 and 15. 1965 - Established by F.J.Bray RLS midway and on line between 1/4 corner to West and Section corner to East. Set 1.25"x30" iron pipe. 8" J.Pine N13E 37.75 links, 7" J.Pine S72W 26.5 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G3) Found the 2" iron pipe of record, in good condition, and at record bearing and distance from the 1958 NBT J.Pine SW, standing dead. The J.Pine NBT NE was not found. This corner is being recorded to update the accessories.

(2-Sec. 15) Found the 1965 monument in good condition and at record bearing and distance from the remaining 1965 BT J.Pine NE, in good condition. This corner is being recorded to update the accessories.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G3) Found 2" T.pipe in firelane intersection. Drove 5/8" x24" rebar with plastic cap "MICH DNR LS33986" into it. Set measuring nail with MDNR tag in the side of:  
 10" J.Pine S83E 49.5' mrkd "S10 NBT"  
 9" J.Pine S12E 36.4' do  
 11" R.Pine N43W 59.35' "S4 NBT"  
 7" R.Pine N67W 77.35' do  
 Bearings are magnetic.

(2) Found 1.25" ID iron pipe. Set measuring nail with MDNR tag in the side of:  
 8" J.Pine N19E 25.35' 1965 BT  
 8" J.Pine N35W 26.8' mrkd "E1/16 BT"  
 8" J.Pine S68E 40.98' do  
 9" J.Pine S12E 29.8' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

