

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49.. NR 10 W. . .

----- Luce ----- COUNTY

DESCRIPTION OF CORNER Witness corner to Meander corner between Sections 4 and 5
on shore of Lake Superior.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap. -----

WITNESSES TO CORNER 18" Y. Pine S 3/4 E 140 Links (NO MBT) .

6" W. Pine S 7 W 108 Links (NO MBT) .

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed by extending section line from 1/4 corner to south.

NOTE: This is a witness corner. Meander corner lies 2.54 chains north in water.

Corner was placed and witnessed on 10 June 1958.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 5-29-59
REGISTERED LAND SURVEYOR