

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49N N.R. 10W


Luce COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 9-16

CORNER MONUMENT 1" pipe with 4" aluminum cap, buried in south wheel track of E.W. firelane.

DATE MONUMENT PLACED AND WITNESSED 10-29-70

WITNESSES TO CORNER..... 18" Red Pine (±S NBT) N55°E 42.7'



13" R. Pine (±S NBT) S6°W 27.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from two stump bottoms, which are remains of the original witnesses; a Y. Pine, N50°E, 40 links and a Y. Pine S24°W, 20 links.

Found a small wood stake, buried at the corner.

Position checks well with corners ½ mile to east and west.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 12-3-70
REGISTERED LAND SURVEYOR