

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49N N.R. 10W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 7-8-17-18

CORNER MONUMENT 1" pipe with 4" aluminum cap, buried in center of E.-W. firelane

DATE MONUMENT PLACED AND WITNESSED 10-29-70

WITNESSES TO CORNER..... 14" Red Pine (S18 NBT) S7°W 31.3'



11" Red Pine (S17 NBT) S42°E 61.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced in former position as located by Marcus Schaaf, R.L.S., when firelane was constructed. Schaaf's iron pipe has been removed by traffic. Found soil disturbed to depth of 36" at corner. Position checks well with corners to East and West.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 12-3-70