

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49N N.R. 10,11W


Luce COUNTY

DESCRIPTION OF CORNER ¼ corner bet. Secs. 31-36

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9-22-70

WITNESSES TO CORNER..... 28" W. Pine (¼S NBT) N30°W 54.5'



14" Cedar (¼S NBT) S40°W 37.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced as set by Marcus Schaaf, R.L.S.

Found 2" iron pipe in place with remains of two original witnesses; a green, soft maple, bearing N21°E, 24 lks. and a cedar stump, bearing N21°W 25 lks.

Found what appears to be an effaced witness, a hemlock about 40' west of the corner.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler REGISTERED LAND SURVEYOR DATE 10-19-70