

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Three Corners



FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. R. 10 W.	13, Sec. 5
2. PROPERTY CONTROLLING IN SECTION	5, T. 49 N. R. 10 W.	14, Sec. 5 D-2a; Auxiliary Meander Corner North of Center
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S. R. E. W.	1/4 Cor.
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11/13 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 13, Sec. 5 SE. 1/16 Corner, Sec. 5.
- 14, Sec. 5 South 1/16 Corner, on East side, Sec. 5.
- D-2A Auxiliary Meander Corner, North of Center 1/4 Corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 13, Sec. 5 Placed Corner at intersection of line, quartering the SE. quarter of Sec. 5.
- 14, Sec. 5 Placed corner midway and on line bet. Sec. Corner to South and 1/4 Corner to North.
- D-2A Placed monument on N-S 1/4 line, 580.5' North of Center of Section 5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 13, Sec. 5; Placed 1" pipe with 4" aluminium cap at corner.
Bearings: 8" Jack Pine S60°E 4.4' and 8" Jack Pine N25°E 13.7' and 8" Jack Pine S86°E 35.2'
- 14, Sec. 5; Buried 1" pipe, in N-S firelane.
Bearings: 14" Red Pine N47°E 76.2' and 17" Red Pine S54°W 89.0'
- D-2A Placed 1" pipe with 4" aluminium cap, 14' South of Escarpment.
Bearings: 13" W. Pine S60°E 4.9' and 13" W. Pine S40°W 21.6'

SIGNED BY: Billy D. Buckler DATE: 11/27/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ DATE: _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY: _____ DATE: _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____