

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Two Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. R. 10 E.	D-2 9, Sec. 5
2. PROPERTY CONTROLLING IN SECTION	T. 49 N. R. 10 E.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11/13 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

D-2 Center 4 Corner, Section 5.

9, Sec. 5 East 1/16 Corner, Section 5.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D-2 Corner placed at intersection of N-S 1/4 Line and E-W 1/4 Line.

9, Sec. 5 Corner placed midway on line bet. Center corner to West 1/4 Corner to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at both corners.

D-2 bearings:

6" Jack Pine N27°30' 19.9'
3" Jack Pine N53°30' 15.0'

9, Sec. 5 bearings:

18" Red Pine N40°30' 40.9'
5" Jack Pine S13°30' 14.5'
7" Jack Pine S83°30' 9.9'

SIGNED BY Billy D. Buckler DATE 11/27/72

Billy D. Buckler
SURVEYOR'S MICHIGAN REGISTRATION NO. 8817 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____