

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. 8. R. 10 E. W.	G-7 H-7
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 8/23 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 G-7 Sec. Cor. 15-16-21-22, set by Geo. H. Cannon, D.S. 1854.
 Bearings were:

Beech 12" N40°E 13 lks. and Balsam 8" S63°E 15 lks.

H-7 1/4 Cor. bet. Secs. 15-22, set by Harvey Kellen, D.S. 1850.

Bearings were:
 Beech 10" N27 1/2°E 40 lks. and Beech 6" S63°E 21 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 G-7 Sec. Cor. re-established by single proportionate measure and on Recorded Bearings, bet. 1/4 Cor. to West and Sec. Cor. to East. Corner lies 6.0' South of E-1 firelane.

H-7 1/4 Corner re-established by single proportionate measure and on Recorded Bearings, bet. Sec. Cor. to East and 1/4 Cor. to West. Corner lies 35.0' North of E-1 firelane.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" pipe with 4" aluminium cap at both corners.

G-7 New Bearings: 18" Red Pine S74°W 28.0' and 22" W. Pine N34 1/2°W 80.1'

H-7 New Bearings: 30" W. Pine S20°E 21.4' and 24" Red Pine N71°E 58.3'

SIGNED BY Billy D. Buckler DATE 1/4/73
 Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 867 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)