

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Three Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>49</u> N. <u>X</u> , R. <u>10</u> E. <u>W.</u>	<u>G-4</u> <u>7-Sec. 9</u> <u>14-Sec. 9</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8/18/1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-4 $\frac{1}{4}$ Cor. bet. Secs: 9-10, set by Geo. H. Cannon, D.S. 1854.
Bearings were:
Hemlock 5" S48°W 29 lks. and Hemlock 12" N47°E 27 lks.
- 7-Sec. 9 North 1/16 Corner, on east side, Sec. 9.
- 14-Sec. 9 South 1/16 Corner, on east side, Sec. 9.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-4 Corner re-established midway and on line bet. two Sec. Cors.
Corner lies on east side of N-S firelane and 35' south of bluff.
- 7-Sec. 9 Corner established midway and on line bet. Sec. Cor. to North and $\frac{1}{4}$ Cor. to South. Corner lies on east side of N-S firelane.
- 14-Sec. 9 Corner established midway and on line bet. Sec. Cor. to South and $\frac{1}{4}$ Cor. to North. Corner lies on east side of N-S firelane.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" pipe with 4" aluminium cap at all three corners.

- G-4 New Bearings:
10" W. Pine N87°E 14.0' and 10" Red Pine S4°E 41.8'
- 7-Sec. 9 Bearings:
8" Jack Pine N45°W 21.9' and 7" Jack Pine N23°E 35.0'
- 14-Sec. 9 Bearings:
12" Red Pine S75°E 26.7' and 14" Red Pine N62½°E 14.1'

SIGNED BY Billy D. Buckler DATE 1/4/73
 Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8837 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)