

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co. Two Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 49 N. S., R. 10 E. W.	K-4 7-Sec. 11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8/11 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K-4 Corner bet. Secs: 11-12, set by Geo. H. Cannon, D.S. 1854.
Bearings:
Sp. Pine 5" N45°W 40 lks and Sp. Pine 5" N45°E 15 lks.
7-Sec. 11 North 1/16 corner, on east side, Sec. 11.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-4 Corner re-established midway and on line bet. two Sec. Cors.
Corner lies 26.7' east of N-S fire lane.
7-Sec. 11 Corner established midway and on line bet. two Sec. Cors. and approx. 100' South and 80' West of bend in the river.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at both corners.
K-4 New bearings:
7" Jack Pine N42°E 18.0' and 7" Jack Pine S5°E 26.0'
7-Sec. 11 Bearings:
12" R. Maple S80°W 66.1' and 18" R. Maple N18°W 13.0'

SIGNED BY Billy D. Buckler DATE 1/4/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____