

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

two Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. 49 N. 8. R. 10 W.	M-9 M-12	Filed <u>6-30 A.D., 1972</u> At <u>3:35 o'clock P.M.</u> File No. <u>48</u> <i>Doris Taylor, Dep</i> Luce County Reg. of Deeds
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 6/1/1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-9 Original Sec. Cor. placed on the range line by John Burt, D.S., Sept. 28, 1841.
Bearings were:
Maple 4" S53°E 19 Links and Maple 5" N31°W 38 Links
- M-12 Original $\frac{1}{4}$ Cor. placed on the range line by John Burt, D.S., Sept. 28, 1841.
Bearings were:
Hemlock 8" at Corner and W. Pine 12" S33°W 38 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-9 Found no evidence of original corner or witnesses, therefore, re-established corner by single proportionate measure along the range line.
- M-12 Re-established $\frac{1}{4}$ Cor. by S.P.M. along the Range Line. All stumps were removed during the early logging days in preparation for a road. The road was never built. Possible stump hole fits for the pine witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9 Placed 1" pipe with 4" aluminum cap at Corner.
New Bearings:
13" W. Pine S10°W 28.2'
9" W. Pine N18°E 54.4'
18" R. Pine N10°W 65.8'
- M-12 Placed 1" pipe with 4" aluminum cap at Corner.
New Bearings:
17" Red Pine N19°W 82.5'
8" Jack Pine S3°W 13.1'

SIGNED BY Billy D. Buckler DATE 6/20/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)