

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 10 W.

----- Luce ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 19-20-29-30 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap buried in fire line.

WITNESSES TO CORNER	<u>7" Jack Pine</u>	<u>N 32° E</u>	<u>41 links</u>
		<u>"S 20 NBT"</u>	
	<u>8" Jack Pine</u>	<u>S 31° W</u>	<u>52½ links</u>
		<u>"S 30 NBT"</u>	
	<u>10" Jack Pine</u>	<u>N 48° W</u>	<u>30 links</u>
		<u>"S 19 NBT"</u>	

-----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from one yellow pine B.T. bearing S 58° E 32 links.  
B.T. stump down with notch and face in evidence.

Corner lies in intersection of fire lines running N-S-E-W.

Corner found by Marcus Schaaf, Reg. surveyor, at the time fire lanes were built.

Corner placed and witnessed December 27, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 12/27/57  
REGISTERED LAND SURVEYOR