

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 10 W.

----- Luce ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 26-27 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 22" W. Pine N 70° E 2 1/2 links -----

"1/4 S NBT"

13" W. Pine S 12° W 3 1/2 links -----

"1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established 1/4 corner by chaining Gov't chainage 10.19 chs. north from original hemlock line tree at 30.01 chs. as per Gov't notes.

Line tree green, 12" diameter. No evidence of original 1/4 corner or B.T.s.

Placed location poster 4 chs. south on road.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 4/12/57  
REGISTERED LAND SURVEYOR