

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 10 W.

Iuce

COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 3-4-9-10
DESCRIPTION OF CORNER MONUMENT 1/2" x 36" iron bar driven 6" below surface
WITNESSES TO CORNER 6" Jackpine N 45° Wc 80 links
"S 4 NBT"
6" Jackpine S 58° W 38 links
7" Jackpine "S 9 NBT"
S 51° E 72 links
"S 10 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced section corner from one yellow pine B.T. bearing S 15° W 73 links. Tree down and in poor condition.

Also found yellow pine B.T. effaced for old corner which is 1.67 chs. west of corrected corner. This corner corrected in re-survey of 1854.

Section corner lies in intersection of N-S-E-W fire lines.

Corner shown to us by B. McTiver, District Forester.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 6/12/52